

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA

TENDER NO : JPS/IP/PT/02/2024

GRAND SUMMARY OF TENDER (ALL QUANTITIES ARE PROVISIONAL)

Description	Page No.	Amount (RM)
PRELIMINARIES AND GENERAL ITEMS	BQ1/1 - BQ1/6	1,720,800.00
OCCUPATIONAL SAFETY AND HEALTH MANAGEMENT	BQ2/1	308,000.00
ENVIRONMENTAL PROTECTION AND ENHANCEMENT	BQ3/1 - BQ3/3	402,350.00
OUTFALL	BQ4/1 - BQ4/4	535,243.00
BEACH NOURISHMENT	BQ5/1	10,627,200.00
BREAKWATER NORTH	BQ6/1 - BQ6/3	8,795,310.00
GROYNE :-		
GROYNE 1	BQ7/1	203,444.00
GROYNE 2	BQ7/2	152,215.00
DESILTING WORKS	BQ8/1	200,000.00
ECOSYSTEM SERVICES	BQ9/1 - BQ9/6	400,050.00
PROVISIONAL SUM	BQ10/1	52,500.00
TOTAL CARRIED TO FORM OF TENDER		23,397,082.00

works shall be completed in 28 Months

cal amount to be carried forward to Form of Tender

Signature of Contractor :

Dua Puluh Tiga Juta, Tiga Ratus Sembilan Puluh Tujuh Ribu
~~Ratus~~ Lapan Puluh Dua

Signature of Contractor :

Name : _____
 IC No. : _____
 Designation : _____
 Address : _____

 Date : _____

Signature of Witness :

Name : _____
 IC No. : _____
 Designation : _____
 Address : _____

 Date : _____

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 1: -PRELIMINARIES AND GENERAL ITEMS

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
	A100	<u>CONTRACTUAL REQUIREMENTS</u>				
		<u>Bond</u>				
A	A111	Performance Bond.	sum	-	-	-
		<u>Insurances</u>				
B	A121	Insurance of the Works.	sum	-	-	25,000
C	A122	Public Liability Insurance.	sum	-	-	10,000
D	A123	SOC'SO/ Workmen Compensation Insurance.	sum	-	-	12,000
		<u>Statutory Obligation</u>				
E	A140	Compliance with laws, regulations or by laws, or any statutory requirements required by statutes gazetted by the Government or any order or directive issued by statutory bodies.	sum	-	-	20,000
	A200	<u>S.O'S REQUIREMENTS</u>				
		<u>Equipment for the S.O / S.O's Representative</u>				
F	A221	Establishment and removal office equipment as per specifications. Equipment to be reverted to the Contractor after completion. Provision of office equipment :-				
		a) Site office (refer specification Section E1 Preliminaries and General)	sum	-	-	56,000
		b) two (2) Nos of Laptop complete with All in One Printer (refer specification Section E1 Preliminaries and General)	sum	-	-	10,000
		c) one (1) Nos of LCD projector & screen (refer specification Section E1 Preliminaries and General)	sum	-	-	4,000
		d) two (2) no of 4-Wheel Drive with competent driver as (refer specification Section E1 Preliminaries and General)	sum	-	-	240,000
		e) one (1) of Motorcycle (refer specification Section E1 Preliminaries and General)	sum	-	-	15,000
		f) one (1) digital camera (refer specification Section E1 Preliminaries and General)	sum	-	-	3,000
		g) one (1) Photostate machine include scanner (A4 & A3) colour and black & white (refer specification Section E1 Preliminaries and General)	sum	-	-	21,000
		h) Consumable items; eg Portable Solid State Drives (SSD), A4 size plain printing paper, A4 size multi colour printing paper, ink cartridge (colours & black) for all printers as required during the contract period, all associated stationaries & A3 size plan printing paper (refer specification Section E1 Preliminaries and General)	sum	-	-	10,000
G	A222	Maintenance of office equipment.	nth	28	1,000	28,000
Page Total carried to Summary of Bill No. 1						454,000

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024
BILL NO. 1: -PRELIMINARIES AND GENERAL ITEMS

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
	A300	<u>PROJECT REQUIREMENTS</u>				
		<u>Equipment for the S.O / S.O's Representative (Cont'd)</u>				
A	A232	Maintain and operate the above vehicles inclusive of fuel, oil, repairs, roadtax, insurances, competent driver and any maintenance required throughout the duration of the contract and any approved extensions of the contract period.	mlh	28	8500	238,000
		<u>Submission of Documents</u>				
B	A254	Work programme in Microsoft Project on a Gantt Chart format and required personnel to update the programme as per specification or as directed by SO. <i>Notes:</i> <i>1. The Contractor's need to consider the fisherman navigation schedule in and out too the sea based on tide level.</i> <i>2. The Contractor's need to make the Gantt Chart based on the project phase according to the Drawing and detail from this project.</i>	sum	-	-	15,000
		<u>Miscellaneous</u>				
C	A261	Progress report in six (6) sets. Rate to include progress photographs.	mlh	28	350	9,800
D	A262	Project signboard as per Drawing	no	3	3,500	10,500
E	A263	As built drawings as per Specifications in five (5) sets.	sum	-	-	25,000
F	A264	Video recording as per specification for every 4 months (Drone video)	sum	-	-	7,000
		<u>Engineering Survey</u>				
		Allow for setting-out of work (include 500m north and 500m south) and establishment of temporary 3 bench marks by qualified and approved licensed Surveyor. Total survey length of 5km with interval of 50m and extent 100m to sea along the project site except extend 250m to the sea at breakwater area only. This survey including initial and final survey for preparation of an existing ground profile, bridge and as built plans and any other additional surveys, including the use of echo sounder hydrographic survey instrumentation, necessary for measuring the quantities of any work executed for measuring the quantities of any work executed as per specification.				
G	A310.1	Survey and setting out by licensed surveyor.	sum	-	-	25,000
H	A310.2	Dilapidation Survey	sum	-	-	18,000
Page Total carried to Summary of Bill No. 1						348,300

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 1: -PRELIMINARIES AND GENERAL ITEMS

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
	A300	<u>PROJECT REQUIREMENTS (CONT'D)</u>				
		<u>Quality Assurance / Quality Control (QA/QC)</u>				
A	A321	QA/QC Plan as specifications or as directed by SO.	sum	-	-	10,000
B	A322	Testing of materials : (concrete test cubes, sample, materials and method of testing as per Specification)	sum	-	-	15,000
		<u>Maintenance of Road and Other Public Properties</u>				
C	A351	Routine maintenance for existing road as per Specification or as directed by SO.	sum	-	-	42,000
D	A360	Clearance of site upon completion.	sum	-	-	7,500
		<u>Safe Working Area</u>				
I	A419	Supply, erection, maintenance and removal of safety buoyant for TM Cable Alignment's Requirement or other Authorities Requirement. After the installation the Contractor should prepare the photograph as a proof of work	sum	-	-	20,000
	A500	<u>CONTRACTOR'S REQUIREMENTS</u>				
		<u>Contractor's Facilities</u>				
		Item shall be deemed to include the provision of water supply, electricity, and sanitary facilities and their continuing operation and/or maintenance.				
F	A519	Establish, construct, maintain and remove upon completion as per detail stated; fixed charge;				
G	A519.1	a) Office complete with fittings and equipment	sum	-	-	50,400
H	A519.2	b) Workmen Accomodations	sum	-	-	56,000
J	A519.3	c) Wash Through (2 nos)	sum	-	-	40,000
		<u>Contractor Superintendence and Facilities</u>				
		<u>Contractor Superintendence</u>				
K	A551	Contractor's supervision and site management team including provision of experience site agent.	sum	-	-	126,000
		<u>Temporary Work</u>				
L	A521	Maintain temporary access roads for duration of contract period; time-related charge	sum	-	-	42,000
Page Total carried to Summary of Bill No. 1						408,400

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 1: -PRELIMINARIES AND GENERAL ITEMS

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
	A300	<u>PROJECT REQUIREMENTS (CONT'D)</u>				
		<u>Services</u>				
		(Notes : The Contractor's shall make sure that the hoarding need to be install by phase of the project according to the Drawing detail and the Contractor's need to re-used (dismantle and re-install) the hoarding to other phase (Length that can be install are = max 400m only). After the completion of the work all the hoarding must be remove from site).				
A	A544.1	Provide hoardings; fixed charges as per drawing No. IP.JPS.BPZP.MEL.14/19	sum	-	-	30,000
B	A547	Provide other services; fixed charges; remove all debris, rubbish and waste from the site and keep the working area clean all the time durig construction period.	sum	-	-	11,000
		<u>Mobilisation and Demobilisation</u>				
C	A560.1	Mobilisation and demobilisation for item below; fixed charge Notes : 1. The Contractor's is required to move the 'Turtle Replica' to the Majlis Perbandaran Alor Gajah (MPAG) and after the construction work is finished, the Contractor is required to bring the replica back to the original place. 2. Contractor's need to make sure that the replica is in a good as original condition.	sum	-	-	20,000
D	A560.2	Mobilisation and demobilisation; fixed charge	sum	-	-	9,000
		<u>LAB REQUIREMENTS</u>				
		Item shall be deemed to include the provision of water supply, electricity, and sanitary facilities and their continuing operation and/or maintenance.				
		Establish, construct, maintain and remove upon completion as per detail stated; fixed charge;				
E	A223.1	a) Lab Test complete with fittings and equipment - Including Sieve analysis and Armour Rock Measurement(dimension & weight)	sum	-	-	150,000
F	A223.2	Removal of laboratory equipment Sieve Analysis (In item (a)). Equipment to be reverted to the Contractor after completion.	sum	-	-	20,000
Page Total carried to Summary of Bill No. 1						243,000

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024
BILL NO. 1: -PRELIMINARIES AND GENERAL ITEMS

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
		<u>Project Management Team</u>				
A	A243	Provide qualified Lab Technician minimum 5 years experience	sum	-	-	55,000
B	A249	Provide qualified 'Marine Risk Assessment' (MRA) with an appoint related specialist.	sum	-	-	55,000
		<u>CLASS C : TRAFFIC MANAGEMENT AND CONTROL</u>				
		<u>Traffic Management Plan</u>				
C	C120	Traffic management plan	sum	-	-	30,000
		<u>Traffic Management Team</u>				
D	C133	Supervisor	man-mth	-	-	70,000
E	C134	Traffic Controller	man-mth	-	-	56,600
Page Total carried to Summary of Bill No. 1						266,600

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 1: -PRELIMINARIES AND GENERAL ITEMS

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
		Summary of Bill No. 1: Preliminaries And General Items				
		Page BQ1/1				454,000
		Page BQ1/2				348,300
		Page BQ1/3				408,900
		Page BQ1/4				243,000
		Page BQ1/5				266,600
Total of Bill No. 1 carried to Grand Summary						1,720,800

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 2: - OCCUPATIONAL SAFETY AND HEALTH MANAGEMENT

(ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
	A400	Occupational Safety and Health Requirements as stipulated in specification for Occupational safety and Health for Engineering Construction works				
		<u>AUTHORITIES REQUIREMENTS</u>				
		<u>Planning for Safety and Health Management</u>				
A	A411.1	Preparation of five (5) copies site safety and health plan (S-Plan) as per Specification	sum	-	-	25,000
B	A411.2	Preparation of Hazard Identification Risk Assessment and Risk Control (HIRARC) for the activities carried out at site. (To be sequent submitted before commencement of each works throughout the contract period).	sum	-	-	15,000
C	A414	Health and Safety report in six (6) sets per month	mtk	28	700	19,600
		<u>Resources for Site Safety</u>				
D	A412.1	Site Safety & Health Officer	man-mth	28	4,000	112,000
E	A412.2	Site Safety Supervisor (SSS) Registered with DOSH to be stationed a minimum of 15 hours a week at the site for entire duration of the construction period.	man-mth	28	3,300	92,400
		<u>Protective Equipment</u>				
F	A413	Provision and maintenance of Personal Protective Equipment to S.O staffs at Site of approved quality. The equipment shall include but not be limited to the following:-				
G	A413.1	a) Provision of ten (10) Safety boots.	sum	-	-	3,500
H	A413.2	b) Complete two (2) First Aid Kit	sum	-	-	1,000
J	A413.3	c) Provision of ten (10) safety helmets	sum	-	-	500
K	A417	Provision and maintenance on the site during the duration of the works, of the adequate safety equipment to be approved by the S.O as follows:				
L	A417.1	a) Warning lights.	sum	-	-	5,000
M	A417.2	b) Fire extinguishers	no	4	500	2,000
N	A417.3	c) Hazard tape.	sum	-	-	2,500
		<u>Safety Signages</u>				
P	A416	Safety Signages as per Malaysian Standard Specification	sum	-	-	15,000
		<u>Safe Working Area</u>				
Q	A419.1	Supply, erection, maintenance and removal on completion of the works, protective and security hoarding as stipulated in Specification	sum	-	-	7,500
R	A419.2	Supply, erection, maintenance and removal of safety barriers for maintaining safe working environment	sum	-	-	7,000
Total of Bill No. 2 carried to Grand Summary						308,000

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO.3: ENVIRONMENTAL PROTECTION AND ENHANCEMENT
(ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
	B100	<u>ENVIRONMENTAL MANAGEMENT PLAN (EMP)</u>				
A	B110	Preparation of Environmental Management Plan which shall include Erosion and Sediment Control Plan (ESCP), noise, air and water quality monitoring and compliance with requirements of the Local Authorities and the Department of Environment.	sum	-	-	50,000
B	B120	Appointment of Certified Environmental Officer (E.O) for the duration of the contract period.	man-mth	-	-	168,000
	B200	<u>EROSION AND SEDIMENT CONTROL (ESCP)</u>				
C	B220	Silt curtain of 2.5m height average as per specification and as shown in the drawings. (re-used every 400m)	sum	-	-	50,000
D	B220	Maintenance of the silt curtain inclusive all necessary and associated works for the duration of the contract as stated in the specification.	sum	-	-	10,000
	B300	<u>ENVIRONMENTAL MONITORING & REPORTING</u>				
		All tests shall be executed by a laboratory accredited by Skim Akreditasi Makmal Malaysia (SAMM).				
	B340	Marine Water Quality Monitoring				
E		To conduct monthly marine water quality monitoring for the parameters listed below. One sample is to be taken at the inside of the silt curtain and one sample from outside of the silt curtain, depending on the work area.	no	56	1,800	100,800
		a) pH (on site) b) Temperature (on site) c) Dissolved Oxygen (on site) d) Chemical Oxygen Demand as COD e) Biological Oxygen Demand as BOD5 f) Total Suspended Solid g) Mercury as Hg h) Cadmium as Cd i) Chromium as Cr6+ j) Arsenic as As k) Lead as Pb l) Copper as Cu m) Iron as Fe n) Cyanide as CN o) Zinc as Zn p) Nitrate as NO3 q) Oil & Grease r) Phenol s) Ammonia as NH3 t) Phosphate as PO4 u) Turbidity v) Conductivity				
Page Total carried to Summary of Bill No. 3						378,800

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO.3: ENVIRONMENTAL PROTECTION AND ENHANCEMENT

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
	B500	NOISE CONTROL AND MONITORING				
A	B531	To conduct noise level sampling and analysed by accredited laboratory once in 3 months (28 months);	nr	9	950	8,550 /
	B800	ENVIRONMENT REPORT				
B	B810	Implementation of Environment Monitoring and submission of monthly report of the implementation of the local department of environment (DOE)'s requirement, as specified in specifications and to the S.O approval.	sum	-	-	15,000
Page Total carried to Summary of Bill No. 3						23,550

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO.3: ENVIRONMENTAL PROTECTION AND ENHANCEMENT

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
		Summary of Bill No. 3: Environmental Protection and Enhancement				
		Page BQ3/1				378,800
		Page BQ3/2				23,550
Total of Bill No. 3 carried to Grand Summary						402,350

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 4 : -OUTFALL

(ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
	A500	<u>CONTRACTOR'S REQUIREMENTS</u>				
		<u>Temporary Work</u>				
A	A524	Provide, maintain and removal of temporary staging, pumping, dewatering and channel diversion for facility construction work, demolish, reinstate back to its original alignment upon completion including making good and complete with original ground finish all as per S.O's instruction, approval and drawing.	Sum	-	-	200,000
B	A529	Contractor shall propose method of work, sequence of work, work programme and cost breakdown for special temporary work to construct outfall and other necessary work inclusive of drawings and PEPC endorsement.	sum	-	-	5,000
		<u>DEMOLITION SITE CLEARANCE</u>				
		<u>General Clearance</u>				
C	E110	General clearance, above ground of existing pipelines including sump and concrete blocks. The sizes are varies (7 locations of pipes) including dismantling and dispose to the Contractor's own dump area.	sum	-	-	7,500
		<u>SUMP</u>				
	F100	<u>EXCAVATION</u>				
D	F131.2	Excavate to required level and dimension for laying of concrete and pipeline concrete as per drawing No. IP/JPS.BP/ZP.MEL.14/14 and specification as directed by S.O.				
		- Sump 1	m ³	4	7	28
		- Sump 2	m ³	4	7	28
		- Sump 3	m ³	4	7	28
		- Sump 4	m ³	4	7	28
		- Sump 5	m ³	4	7	28
		- Sump 6	m ³	2	7	14
		- Sump 7	m ³	2	7	14
Page Total carried to Summary of Bill No. 4						212,668

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 4 : -OUTFALL

(ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
A		Sump (Cont')				
	F300	<u>FILLING</u>				
	F359	Hardecore	m ³	5	65	325
	1100	<u>IN-SITU CONCRETE DESIGN MIX</u>				
		Rate for in situ concrete designed mix (Pulverised Fuel Ash (PFA)) as specified shall be deemed to include placing and compaction of concrete.				
		Grade: C15				
B	1111.1	Concrete blinding mass Grade C15, 50mm thick.	m ²	30	25	750
		Grade: C30				
C	1142.4	Ground slabs	m ³	8	350	2,800
D	1145.2	Walls	m ³	28	350	9,800
E	1148	Concrete blocks	m ³	24	350	8,400
	1500	<u>FORMWORK</u>				
		Rate for formwork shall be deemed to include the projections and intrusions and any temporary staging required.				
F	1514.1	F2: Fair finish to all structural component.	m ²	110	40	4,400
	1600	<u>REINFORCEMENT</u>				
		Rate for reinforcement shall be deemed to include labour for cutting, bending, and placing				
		Mild steel bars				
G	1612	Nominal diameter : 8mm	t	1.0	4,200	4,200
H	1613	Nominal diameter : 10mm	t	6.0	4,200	25,200
		Grating Sump				
J	O629.1	Size 1200mm x 1200mm	no	5	1,500	7,500
K	O629.2	Size 900mm x 900mm	no	2	1,300	2,600
		<u>OUTFALL PIPE</u>				
		<u>EXCAVATION</u>				
L	F131.2	Excavate to required level and dimension for laying of concrete and pipeline concrete as per drawing No. IP.JPS.BPZP.MEL.14/1 and specification as directed by S.O.	m ³	1000	7	7,000
Page Total carried to Summary of Bill No. 4						72,975

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 4 : -OUTFALL

(ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
		OUTFALL PIPE (Cont')				
	O500	<u>PIPE</u>				
		High density corrugated polyethylene (HDPE) Class F solid wall plain ended pipe to MS 1058 including thermal extrusion welded joint (wet area) and elastomeric ring joint (dry area) as per specification.				
A	O533.1	600m dia.	m	60	400	24,000
B	O533.2	750m dia.	m	170	630	107,100
C	O533.3	900m dia.	m	60	1,050	63,000
	O300	<u>BACKFILING AND BEDDING, SUPPORT AND PROTECTION</u>				
		Backfilling				
D	O311.1	Sand as per specification - Final backfill (reused excavated material)	m ³	750	50	37,500
		Haunches				
		Haunches with imported granular (crusher run) materials as per specifications and as shown in Drawing No. IP.JPS.BPZP.MEL.14/15 :-				
E	O343.1	600m dia.	m ³	30	75	2,250
F	O343.2	750m dia.	m ³	140	75	10,500
G	O343.3	900m dia.	m ³	70	75	5,250
Page Total carried to Summary of Bill No. 4						249,600

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 4 : -OUTFALL

(ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
		Summary of Bill No. 4: Outfall				
		Collected Page:				
		BQ4/1				212,668
		BQ4/2				72,975
		BQ4/3				249,600
Total of Bill No. 4 carried to Grand Summary						535,243

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024
BILL NO. 5 : BEACH NOURISHMENT
(ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
		<u>BEACH NOURISHMENT</u>				
		Notes :				
		This Bill shall be read in conjunction with the Specification, Preliminaries and Preambles to all Trades attached.				
		The Contractor's need to take consideration of the turtle landing season between April to October during the construction period.				
		The Contractor's must make a work plan for 3 phases involving the width of the beach nourishment which is 50m, 30m and 30m width at cable area as indicated in the Drawing IP.JPS.BPZP.MEL.14/04, IP.JPS.BPZP.MEL.14/05 -1 - 13, IP.JPS.BPZP.MEL.14/06 & IP.JPS.BPZP.MEL.14/07-1 - 13				
	F300	FILLING				
	F312	Imported sand material from Contractor's own sources with grading limit (size 0.8mm - 1.2mm with minimum 50% from overall quantity shall be of 0.8mm) and to form proposed Beach nourishment design level as per engineer's specification including all related works for proper completion, including barge, pumps, hoses and etc. and settlement topping up within the construction period as per S.O's instruction if necessary.				
A	F312.1	a) 50m width section	m ³	222,000	36	7,992,000
B	F312.2	b) 30m width section	m ³	68,400	36	2,462,400
C	F312.3	b) 30m width section- cable area	m ³	4,800	36	172,800
Total of Bill No. 5 carried to Grand Summary						10,627,200

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 6 : BREAKWATER

(ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
		<u>BREAKWATER</u>				
	F300	FILLING				
A	F312.1	Imported material (Earth fill) from Contractor's own source with grading limits as per specification.	m ³	2,820	35	98,700
B	F312.2	Imported sand material from Contractor's own sources with grading limit as per specification and Engineer's Drawing No. IP.JPS.BPZP.MEL.14/10 (size 0.8mm - 1.2mm with minimum 50% from overall quantity shall be of 0.8mm) and to form proposed design level including quantities for settlement topping up throughout construction period as per SO's instruction only when the finish level settled lower than 2.5m.	m ³	85,000	36	3,060,000
C	F354.1	1.94m thick 2 layers of primary armour lay as per specifications and Engineering Drawing No. IP.JPS.BPZP.MEL.14/10 to form breakwater's primary armour layer. (1800-3000kg granite stones with minimum 50% from overall quantity shall be of 2400kg) including quantities for settlement topping up throughout construction period as per SO's instruction only when the finish level settled lower than 2.5m.	m ³	19,100	150	2,865,000
D	F354.2	0.90m thick of secondary layers 160-240kg granite stones lay and compacted as per specifications to form breakwater including quantities for settlement topping up throughout construction period as per SO's instruction only when the finish level settled lower than 2.5m.	m ³	11,500	100	1,150,000
E	F354.3	Lay and compacted of core materials (granite stone 2kg-25kg) layers as per specifications to form breakwater.	m ³	5,200	70	364,000
F	F354.4	Supply, deliver and install woven polypropylene geotextile with Wide Width Tensile Strength (ISO 10319) MD = 200kN/m & CD = 200kN/m and Tensile Strength retention minimum 90% of the pristine sample, CBR Puncture Strength (ISO 12236) = 22kN or equivalent all as per engineer's drawing & material specification.	m ²	20,150	27	544,050
Page Total carried to Summary of Bill No. 6						8,081,750

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 6 : BREAKWATER

(ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
		<u>BREAKWATER USING GEOTUBE</u>				
		<u>Notes :-</u>				
		This section is to be read in conjunction with the specification and the Drawings. The word 'as described' wherever used in this section shall mean as described in the above documents.				
		Should there be any discrepancy found between this section and the Drawings/Specification, the Contractor should immediately inform the S.O who shall then clarify which shall prevail.				
A	G110.1	Allow for the provision of all necessary equipment and tools for their transportation to site, handling, lifting, assembling and removal off the site after completion of all installation works.	sum	-	-	20,000
B	G120	Allow for handling and moving machinery and equipment about the site as often and whenever necessary for the whole operation including idling time and all nessary temporary work in connection there with ; provide hardstanding including taking up and reinstall as the work progress.	sum	-	-	15,000
		<u>GEOTUBE PROTECTION SYSTEM</u>				
C	G490	Supply, deliver and install approved Geotube with circumference of 15.7m and 25m length, or equivalent to Wide Width Tensile Strength (ISO 10319) MD = 200kN/m & CD = 200kN/m and Tensile Strength retention minimum 90% of the pristine sample after 500 hours of UV exposure (ASTM D4355), Abrasion Resistance (ASTM D4886) at least 80%, all as per engineer's drawing & material specification including all necessary works for proper completion. The Geotube shall be 100% locally made in Malaysia.	Unit	9	54,000	486,000 ✓
D	G110.2	Provide all necessary machineries to supply, deliver and fill the approved Geotube or equivalent with approved sands as per engineer's specification including all related works for proper completion, including barge, pumps, hoses and etc.	sum	-	-	30,000
E	F354.1 G800	Supply sand from Contractor own's source similar to beach nourishment sand specifications for Geotube filling.	m³	3,960	36	142,560 ✓
		INSTRUMENTATION				
F	G890.1	Settlement marker as shown in the drawings No. IP.JPS.BPZP.MEL.14/17	no	6	1,000	6,000 ✓
G	G890.2	Settlement gauge as per specification and as shown in the drawings No. IP.JPS.BPZP.MEL.14/17	no	4	3,500	14,000
Page Total carried to Summary of Bill No. 6						713,560

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 6 : BREAKWATER

(ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
		Summary of Bill No. 6: Breakwater				
		Collected Page:				
		BQ6/1				8,081,750
		BQ6/2				713,560
Total of Bill No. 6 carried to Grand Summary						8,795,310

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.
TENDER NO : JPS/PP/PT/02/2024
BILL NO. 7 : TERMINAL GROVNE 1 & 2
(ALL QUANTITIES ARE PROVISIONAL.)

Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
	TERMINAL GROVNE 1 & 2 AT SG TUANG				
	FILLING				
	Head				
F354.1	2.0m thick 2 layers of primary armour lay as per specifications and Engineering Drawing No. IP.JPS.BPZP.MEL.14/09 to form groyne primary armour layer. (1800-3000kg granite stones with minimum 50% from overall quantity shall be of 2400kg) including quantities for settlement topping up within the construction period as per S.O instruction to maintain minimum design level of 2.3m at the end of project.	m ³	276	150	41,400
F354.2	0.90m thick of secondary layers 160-240kg granite stones lay and compacted as per specifications to form groyne including quantities for settlement topping up within the construction period as per S.O instruction to maintain minimum design level of 2.3m at the end of project.	m ³	311	100	31,100
F354.3	Lay and compacted of core materials (granite stone 2kg-25kg) layers as per specifications to form groyne.	m ³	17	70	1,190
F354.4	Supply, deliver and install woven polypropylene geotextile with Wide Width Tensile Strength (ISO 10319) MD = 200kN/m & CD = 200kN/m and Tensile Strength retention minimum 90% of the pristine sample, CBR Puncture Strength (ISO 12236) = 22kN or equivalent all as per engineer's drawing & material specification.	m ²	587	27	15,849
	Trunk				
F354.5	2.0m thick 2 layers of primary armour lay as per specifications and Engineering Drawing No. IP.JPS.BPZP.MEL.14/09 to form groyne primary armour layer. (1800-3000kg granite stones with minimum 50% from overall quantity shall be of 2400kg) including quantities for settlement topping up within the construction period as per S.O instruction to maintain minimum design level of 2.3m at the end of project.	m ³	368	150	55,200
F354.6	1.3m thick of secondary layers 160-240kg granite stones lay and compacted as per specifications to form groyne including quantities for settlement topping up within the construction period as per S.O instruction to maintain minimum design level of 2.3m at the end of project.	m ³	343	100	34,300
F354.7	Supply, deliver and install woven polypropylene geotextile with Wide Width Tensile Strength (ISO 10319) MD = 200kN/m & CD = 200kN/m and Tensile Strength retention minimum 90% of the pristine sample, CBR Puncture Strength (ISO 12236) = 22kN or equivalent all as per engineer's drawing & material specification.	m ²	573	27	14,175
G800	INSTRUMENTATION				
G890.1	Settlement marker as shown in the drawings No. IP.JPS.BPZP.MEL.14/17	nos	3	3,000	6,000
G890.2	Settlement gauge as per specification and as shown in the drawings No. IP.JPS.BPZP.MEL.14/17	nos	4	4,000	14,000
Total of Bill No. 7a carried to Grand Summary					203,474

... or a pipe being jacked, a thrust ring is used to ... the loads. The jacks are interconnected hydraulically to ... the thrust from each is the same. The number of jacks used ...

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 7 : TERMINAL GROUYNE 1 & 2

(ALL QUANTITIES ARE PROVISIONAL.)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
		TERMINAL GROUYNE (2) AT SG TUANG				
	F300	FILLING				
		Head				
A	F354.1	2.0m thick 2 layers of primary armour lay as per specifications and Engineering Drawing No. IP.JPS.BPZP.MEL.14/09 to form groyne primary armour layer. (1800-3000kg granite stones with minimum 50% from overall quantity shall be of 2400kg) including quantities for settlement topping up within the construction period as per S.O instruction to maintain minimum design level of 2.3m at the end of project.	m ³	276	150	41,400
B	F354.2	0.90m thick of secondary layers 160-240kg granite stones lay and compacted as per specifications to form groyne including quantities for settlement topping up within the construction period as per S.O instruction to maintain minimum design level of 2.3m at the end of project.	m ³	311	100	31,100
C	F354.3	Lay and compacted of core materials (granite stone 2kg-25kg) layers as per specifications to form groyne.	m ³	17	70	1,190
D	F354.4	Supply, deliver and install woven polypropylene geotextile with Wide Width Tensile Strength (ISO 10319) MD = 200kN/m & CD = 200kN/m and Tensile Strength retention minimum 90% of the pristine sample, CBR Puncture Strength (ISO 12236) = 22kN or equivalent all as per engineer's drawing & material specification.	m ²	587	27	15,849
		Trunk				
E	F354.5	2.0m thick 2 layers of primary armour lay as per specifications and Engineering Drawing No. IP.JPS.BPZP.MEL.14/09 to form groyne primary armour layer (1800-3000kg granite stones with minimum 50% from overall quantity shall be of 2400kg) including quantities for settlement topping up within the construction period as per S.O instruction to maintain minimum design level of 2.3m at the end of project.	m ³	184	150	27,600
F	F354.6	1.3m thick of secondary layers 160-240kg granite stones lay and compacted as per specifications to form groyne including quantities for settlement topping up within the construction period as per S.O instruction to maintain minimum design level of 2.3m at the end of project.	m ³	173	100	17,300
G	F354.7	Supply, deliver and install woven polypropylene geotextile with Wide Width Tensile Strength (ISO 10319) MD = 200kN/m & CD = 200kN/m and Tensile Strength retention minimum 90% of the pristine sample, CBR Puncture Strength (ISO 12236) = 22kN or equivalent all as per engineer's drawing & material specification.	m ²	288	27	7,776
	G800	INSTRUMENTATION				
H	G890.1	Settlement marker as shown in the drawings No. IP.JPS.BPZP.MEL.14/17	no	2	3000	6,000
J	G890.2	Settlement gauge as per specification and as shown in the drawings No. IP.JPS.BPZP.MEL.14/17	no	1	4000	4,000
Total of Bill No. 7b carried to Grand Summary						152,215

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024
 BILL NO. 8 : DESILTING WORKS
 (ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
		<u>DESILTING WORKS</u>				
	F100	<u>EXCAVATION</u>				
		Excavate to required level and dimension to remove the fine silt and sediment that has been collected in the river, in order to restore its natural capacity, without widening or deepening of the river and to make sure the flow of the river is perfect (4 times) as directed by S.O. if necessary only at the beginning(1x), during(1x), at the end (CPC) of the project (1x) and at the end of DLP period (1x).				
		(For estuary section Sg. Tuang, Sg Kertah and Sg Ayer Hitam) as per drawing and specification as directed by S.O.				
A	F131.1	(a) During construction (3 times):				
		-Sg. Tuang	m ³	6,000	10	60,000
		-Sg. Ayer Hitam	m ³	3,000	10	30,000
		-Sg. Kertah	m ³	6,000	10	60,000
B	F131.2	(b) During Defect Liability Period (DLP) period.(1 time)				
		-Sg. Tuang	m ³	2,000	10	20,000
		-Sg. Ayer Hitam	m ³	1,000	10	10,000
		-Sg. Kertah	m ³	2,000	10	20,000
Total of Bill No. 8 carried to Grand Summary						200,000

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024
 BILL NO. 9 : ECOSYSTEM SERVICES
 (ALL QUANTITIES ARE PROVISIONAL)

Description	Unit	Qty.	Rate (RM)	Amount (RM)
SOFT LANDSCAPE WORKS				
To supply, deliver and plant trees as noted and directed to site including handling, hoisting, excavating planting holes/trench with other related and necessary work as directed by L.A / S.O				
Planting Hole				
To supply equipment, labour, tools, transportation and etc. for planting works to the following plants inclusive of excavating suitable sized holes and carting away all excavating materials.				
a) Trees / Palm (1m x 1m x 1m)	no	360	20	7,200
b) Shrub (450mm x 450mm x 450mm)	no	2000	10	20,000
Soil Mixture				
To supply and deliver soil mixture of 3 parts top soil, 2 parts cocoa peat, and 1 part organic fertilizer.				
3 : Top Soil				
2 : Coco Peat				
1 : Organic Fertilizer (1kg BIO-CHAR / tree)				
a) Trees / Palm	m ³	360	40	14,400
b) Shrubs	m ³	200	10	2,000
Staking				
Supply and install wood staking for all trees and palms. The wood staking should be pegged into the planting hole (H-type) and painted with green color. All works should follow as according to the specification or to the satisfaction and approval of the Landscape Architect (L.A) and Superintending Officer (S.O)				
a) Trees / Palm (50mm x 50mm x 2500mm)	Set	360	20	7,200
Mulching				
To supply, deliver and lay 50mm thick coco fiber around the planted plants as stated in planting plan and directed by Landscape Architect/S.O.				
a) Trees / Palm (1m x 1m x 1m)	no	360	10	3,600
b) Shrub (450mm x 450mm x 450mm)	no	2000	10	20,000
Watering Bag				
To supply, deliver and install the tree watering bag around the planted plants, at least 500mm-650mm from the ground and directed by Landscape Architect/S.O.				
a) Trees / Palm (1m x 1m x 1m)	no	360	50	18,000
				92,400

Page Total carried to Summary of Bill No. 9

B9/1

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

**TENDER NO : JPS/IP/PT/02/2024
BILL NO. 9 : ECOSYSTEM SERVICES
(ALL QUANTITIES ARE PROVISIONAL)**

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
1.7		SOFT LANDSCAPE WORKS (Contd) Tree Guard Protection Supply, deliver and install the tree guard protection around the planted plants, with a round size of 1m diameter and 1m height. The tree guard should be from HDPE plastic tree guard with green/black color. All works should follow as according to the specification or to the satisfaction and approval of the Landscape Architect (L.A) and Superintending Officer (S.O)				
		a) Trees / Palm (1m x 1m x 1m)	no	360	80	28,800
1.8		Tree Hardening To supply equipment, labour, tools, transportation and etc, for hardening works which include watering, weeding, mulching, pruning and repair, grass cutting and removal of grass clippings, and fertilizing to the following plants about three weeks after the particular plant brought on site. Tree hardening is the process of allowing a plant to transition from a protected indoor or greenhouse environment to the harsh outdoor conditions of fluctuating spring temperatures, wind, and full sun exposure. All works should follow as according to the specification or to the satisfaction and approval of the Landscape Architect (L.A) and Superintending Officer (S.O)				
		a) Trees / Palm (1m x 1m x 1m)	no	360	80	28,800
Page Total carried to Summary of Bill No. 9						57,600

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024
 BILL NO. 9 : ECOSYSTEM SERVICES
 (ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
1.9		SOFT LANDSCAPE WORKS (Contd)				
		Softscape Planting				
		Supply and plant trees/shrub according to the specifications given. All plants materials should be free from all diseases, infertility and have a straight trunk				
1.9.1		Trees				
		a) <i>Barringtonia asiatica</i> (Pokok Putat Laut) Clear Trunk Height : 2.5m Trunk Dia. : 50mm	no	32	420	13,440
		b) <i>Calophyllum inophyllum</i> (Pokok Penaga Laut) Clear Trunk Height : 2.5m Trunk Dia. : 50mm	no	37	400	14,800
		c) <i>Cinnamomum porrectum</i> (Pokok Medang Sarsi) Clear Trunk Height : 2.5m Trunk Dia. : 50mm	no	35	380	13,300
		d) <i>Guetarda speciosa</i> (Pokok Ketapang Pasir) Clear Trunk Height : 2.0m Trunk Dia. : 50mm	no	33	400	13,200
		e) <i>Melaleuca cajuputi</i> (Pokok Gelam) Clear Trunk Height : 3.0m Trunk Dia. : 50mm	no	20	380	7,600
		f) <i>Millettia pinnata</i> (Pokok Pongam) Clear Trunk Height : 2.5m Trunk Dia. : 50mm	no	25	410	10,250
		g) <i>Syzygium campanulatum</i> (Pokok Kelat Paya) Clear Trunk Height : 2.5m Trunk Dia. : 50mm	no	30	460	13,800
		h) <i>Syzygium grande</i> (Pokok Jambu Laut) Clear Trunk Height : 2.5m Trunk Dia. : 50mm	no	26	400	10,400
		i) <i>Syzygium gratum</i> (Pokok Gelam Tikus) Clear Trunk Height : 2.5m Trunk Dia. : 50mm	no	28	530	14,840
		j) <i>Terminalia catappa</i> (Pokok Ketapang) Clear Trunk Height : 3.0m Trunk Dia. : 50mm	no	32	400	12,800
		k) <i>Thespesia populnea</i> (Pokok Bebaru) Clear Trunk Height : 2.5m Trunk Dia. : 50mm	no	10	410	4,100
		Page Total carried to Summary of Bill No. 9				128,850

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

**TENDER NO : JPS/IP/PT/02/2024
BILL NO. 9 : ECOSYSTEM SERVICES
(ALL QUANTITIES ARE PROVISIONAL)**

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
1.9.2		Palm				
		a) <i>Cocos nucifera</i> (Kelapa) Clear Trunk Height : 2.1m Trunk Dia. : 50mm	no	12	350	4,200
1.9.3		Plants For Island Breakwater				
1.9.3.1		Trees				
		a) <i>Thespesia populnea</i> (Pokok Bebaru) Clear Trunk Height : 2.5m Trunk Dia. : 50mm	no	40	500	20,000
1.9.3.2		Shrubs				
		a) <i>Scaevola taccada</i> (Ambong-ambong) Overall Height : 600mm Planting Dist. : 300-450mm	no	2000	15	30,000
1.9.3.3		Turfing				
		Supply equipment, labor and other related items for carrying out the turfing works of <i>Axonopus compressus</i> (cow grass) Works include supply, install, level and flattened top soil for about 100mm thick.				
		(a) <i>Axonopus compressus</i> (Cow Grass)	m ²	2000	3.50	7,000
		Page Total carried to Summary of Bill No. 9				61,200

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

**TENDER NO : JPS/IP/PT/02/2024
BILL NO. 9 : ECOSYSTEM SERVICES
(ALL QUANTITIES ARE PROVISIONAL)**

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
2.0		Soft Landscape and Hardscape Maintenance Works During the period, contractor are to provide equipment, labor and all related works for a period of twelve (12) months commencing upon the date of practical completion. (a) Watering Provide tree watering bag that easily attached to the tree with a smooth-running zipper and filled with a hose, at least 500mm-650mm from the ground. Drop by drop, 75 liters are released into the ground for up to 9 hours through tiny holes in the ground. Watering should be done (fill the bag) 1 to 2 times per week, depends on weather conditions on site. (b) Weeding Keep all planting area free from weeds undesirable grasses by method and materials. For groundcovers, all weeds that grow within and surrounding the plants should be removed. For shrubs, it is advisable to clear the weeds up to 30cm surrounding the main of shrubs. for young trees and palms, its can be done for approximately 45 cm from the main trunk. (c) Mulching Apply suitable mulches i.e cocopeat or equivalent to all planting area or as specified (once every two months) (d) Pruning and Repair The amount of pruning shall be limited to the minimum necessary to remove dead or injury twigs and branches. (e) Grass cutting and removal of grass clippings. <u>Twice a month. Shall be done in the first and third week.</u> (f) Fertilizing All trees need to be supply with an approved organic fertilizer or a slow release fertilizer, apply accordingly to the manufacturer instruction. It has to be done after grass cutting and pruning. Keep all area clean and tidy, free from rubbish. All waste materials shall be continuously and promptly removed and all reasonable precaution taken to avoid damage to existing plants and grass. Notes : The contractor are to submit a complete twenty four (24) set of report that contain 12 photos by 3R size for each report and comes with written description of the maintenance activities that being carried out.	nth	12	5,000	60,000
Page Total carried to Summary of Bill No. 9						60,000

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024

BILL NO. 9 : ECOSYSTEM SERVICES
(ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate (RM)	Amount (RM)
		Collected Page:				
		BQ9/1				92,400
		BQ9/2				57,600
		BQ9/3				128,850
		BQ9/4				61,200
		BQ9/5				60,000
		Total of Bill No. 9 carried to Grand Summary				400,050 ✓

PROJEK PENGAWALAN HAKISAN PANTAI PENGKALAN BALAK, DAERAH ALOR GAJAH, MELAKA.

TENDER NO : JPS/IP/PT/02/2024
 BILL NO. 10 : PROVISIONAL SUM
 (ALL QUANTITIES ARE PROVISIONAL)

Item No.	Code No.	Description	Unit	Qty.	Rate	Amount (RM)
	W100	<u>PROVISIONAL SUM</u>				
A	W110	Provisional Sum of (RM50,000.00 Fifty Thousand Only for Beacon lamp - 3 nos)	sum	-	-	50,000.00
B	W210	Attendance	sum	-	-	1,250
C	W220	Profit	%			1,250
Total of Bill No. 11 carried to Grand Summary						52,500