

SUMMARY OF TENDER AND BILL OF QUANTITIES

**PROJECT: PENGURUSAN DAN PENYELENGGARAAN JALAN-JALAN PIHAK BERKUASA
TEMPATAN SECARA BERSEPADU SELURUH NEGERI JOHOR**

PBT	Majlis Perbandaran Kluang
Package	SGV/MPK/LA/NPV/2024/026
Contract Sum (RM)	602,902.40
Date of Commencement	22 April 2024
Date of Completion	22 August 2024
LAD	0.02% from Original Contract Sum with minimum amount RM50.00 per day
DLP	Twelve (12) months
Retention Money	FIVE PERCENTUM (5%) from the Sub-Contract Amount for any defects arising in the service(es) under this Sub-Contract and/or to any incomplete services within the Defect Liability Period.
On-Cost charges for the supply of materials to the Sub-Contractor by the Main Contractor	3.00%
On-Cost charges by engaging others to complete the Sub-Contract Works	25.00%
Number of days of default	To be advised by site representative of the Main Contractor





SAFWA GLOBAL VENTURE (M) SDN. BHD.

Our Ref : SGV/MPK/LA/NPV/2024/026

Date : 04 APR 2024

Sub-Contractor : EFFA ENTERPRISE

WISMA AL-FIRDAUS , LOT 1131, BATU 45, JALAN JOHOR

86200 Kluang

Johor

Commencement Date : 22/04/2024

Completion Date : 22/08/2024

Completion Period : Week/Days

Project : PENGURUSAN DAN PENYELENGGARAAN JALAN-JALAN PIHAK BERKUASA TEMPATAN SECARA BERSEPADU DI SELURUH NEGERI JOHOR

Title : SLOPE WORK WITH CRIBWALL AT JALAN KLUANG INDAH 2/8, TAMAN KLUANG INDAH IN THE DISTRICT OF KLUANG, JOHOR

SUMMARY OF QUANTITIES

Items are provisional quantity. Final quantity shall subject to join measurement on site.

Scope of Work				Unit	Qty	Day	Amount SUB (RM)	
Item	Sub-Item	Item ID	Item Descriptions				Rate	Amount
Pavement And Shoulder	Milling	1.4.4	Milling of existing pavement surface including clean and remove all debris to receive new surface overlay 101mm - 150mm depth from existing surface	m2	280.00	-	6.00	1,680.00
Pavement And Shoulder	Regulating	1.5.1	Supply and apply bituminous prime coat uniformly to surface of binder course including cleaning the surface of pavement prior to application.	m2	280.00	-	1.50	420.00
Pavement And Shoulder	Regulating	1.5.4	Supply, lay and compact asphaltic concrete 28 binder course (AC 28).	MT	23.000	-	240.00	5,520.00
Pavement And Shoulder	Resurfacing	1.6.1	Supply and apply bituminous tack coat uniformly including cleaning the surface of pavement prior to application.	m2	280.00	-	1.40	392.00
Pavement And Shoulder	Resurfacing	1.6.2	Supply, lay, spread, level and compact Asphaltic Concrete 14 Wearing Course (AC 14).	m3	14.00	-	580.00	8,120.00
Drainage	Drain and Culvert	5.1.4	Sawn formwork.	m2	3.00	-	32.00	96.00
Drainage	Drain and Culvert	5.1.5	Excavate trenches in all material other than rock for precast concrete pipe culvert, backfill and remove surplus spoil to a tip to be provided by the Contractor away from work site within 5 km radius including all necessary timbering - not exceeding 1.50	m3	79.00	-	7.20	568.80
Drainage	Drain and Culvert	5.1.10	Supply and lay site mix Grade 15 concrete (1: 3 : 6) as blinding.	m3	5.25	-	226.00	1,186.50
Drainage	Drain and Culvert	5.1.11	Supply and lay site mix Grade 20 concrete (1 : 2 : 4) as bedding.	m3	13.00	-	230.40	2,995.20
Drainage	Drain and Culvert	5.1.12	Supply and lay site mix Grade 30 concrete as bedding.	m3	8.00	-	280.00	2,240.00
Drainage	Drain and Culvert	5.1.23	Supply, fabricate and lay steel fabric reinforcement of the following size : B.R.C. (BS 4483) - A8	m2	74.00	-	24.00	1,776.00
Drainage	Drain and Culvert	5.1.25	Supply, fabricate and lay steel fabric reinforcement of the following size : B.R.C. (BS 4483) - A10	m2	296.00	-	32.00	9,472.00
Drainage	Drain and Culvert	5.1.50	Supply and lay 20mm thick cement and sand (1 : 3) plastering.	m2	223.00	-	13.50	3,010.50
Drainage	Drain and Culvert	5.1.60	Supply and lay spun butt and rebate joint precast reinforced concrete pipe culverts class Y in trench of the following size: 450mm diameter.	m	6.00	-	192.00	1,152.00
Drainage	Drain and Culvert	5.1.80	Supply, lay, level and compact crushed aggregate to formation level.	m3	212.00	-	75.00	15,900.00
Drainage	Precast Concrete U-Shaped Drain with Dry Weather Flow	5.2.53	Supply and lay precast reinforced concrete U-Shaped Drain With Dry Weather Flow for the following sizes :- 450mm width x 450mm height	m	75.00	-	150.00	11,250.00
Slope Repairs And Slope Stabilisation	Site Clearing	7.1.1	Site clearing of the required width of undergrowth bushes, shrubs, grass etc, remove and dispose.	m2	1,500.00	-	1.50	2,250.00

Scope of Work				Unit	Qty	Day	Amount SUB (RM)	
Item	Sub-Item	Item ID	Item Descriptions				Rate	Amount
pe Repairs And pe Stabilisation	Geotextiles	7.6.2.1	Close turfing at any inclination to slopes, medians, berms and verge (Cow grass)	m2	400.00	-	5.80	2,320.00
pe Repairs And pe Stabilisation	Crib Wall	7.11.2	Excavation for cribwall block, R.C. footing, temporary slope including cart away excess earth from site.	m3	720.00	-	8.40	6,048.00
pe Repairs And pe Stabilisation	Crib Wall	7.11.7	Sawn formwork for R.C. footing.	m2	27.00	-	32.20	869.40
pe Repairs And pe Stabilisation	Crib Wall	7.11.11	Supply and compact by tamping approved well graded, clean and free draining infill material within cribwall block.	m3	803.00	-	75.00	60,225.00
uctures	Retaining Wall And Other Protection Structures	8.2.2	Remove unsuitable excavated earth from site.	m3	50.00	-	29.20	1,460.00
uctures	Retaining Wall And Other Protection Structures	8.2.3	Backfill and compact excavated suitable earth (on site earth) behind and on top of Key Wall.	m3	670.00	-	14.00	9,380.00
uctures	Retaining Wall And Other Protection Structures	8.2.7	Import, backfill and compact sand fill as well fill material in keystone block and behind Keystone block.	m3	250.00	-	70.00	17,500.00
eme Traffic nagement Plan	Traffic Management Plan	14.1.1	Supply and apply traffic management scheme at site including cone, temporary signboard, blinkers and signalman at site not exceeding 500m	-	30.00	-	500.00	15,000.00
eed Rate - Drainage	Dismantle existing U- shaped drain	19.3.1	Break up, excavate, haul and dispose the damaged existing U-shaped drain not exceeding 600mm width	m	75.00	-	40.00	3,000.00
eed Rate - Drainage	Precast U-shape drain with dry weather flow	19.23.1	Supply and lay precast U-shape drain with dry weather flow for size 300mm width x 300mm Height	m	40.00	-	119.00	4,760.00
eed Rate - Drainage	Concrete	19.25.2	Supply and lay ready mix concrete Grade 35	m3	45.00	-	316.00	14,220.00
eed Rate - Slope pairs And Slope bilisation	Weep Holes	22.2.2	Supply and install 75mm diameter PVC as weepholes at spacing 3000mm c/c including filter cloth wrap with non-woven geotextile	No	40.00	-	12.40	496.00
eed Rate - Slope pairs And Slope bilisation	Stone Pitching	22.3.1	Supply and lay 6" x 9" stone pitching wall in cement and sand (1 : 3) mortar including jointing and pointing	m3	10.00	-	217.50	2,175.00
reed Rate - Slope pairs And Slope bilisation	Crib Wall	22.26.1	Provision for mobilization and demobilization including of all necessary equipment, plant, tools and ancillary equipment and for their transportation to site, handling, assembling, including setting up, erection, dismantling and removal on site for cribwall works	LS	1.00	-	5,000.00	5,000.00
reed Rate - Slope pairs And Slope bilisation	Crib Wall	22.26.3	To supply, deliver and install cribwall component consisting of header and stretcher for the following height ; Triple Cell Header exceeding 8.0m but not exceeding 10.0m	m2	348.00	-	1,100.00	382,800.00
reed Rate - Structure	Brickwall	23.1.2	225mm thick brickwall in common bricks in cement mortar (1:3)	m2	148.00	-	65.00	9,620.00
TOTAL								602,902.40

